

# Timber module school build using modular system

Zug, CH



# Timber module school build using modular system

Zug, CH



## Project details

Client	Stadt Zug
Architecture	Bauart Architekten und Planer AG
Project type	Education and research, Temporary buildings
Construction type	Modular construction
Services	General contractor services (GC)
Construction	2013
Locality	Zug
Country	Switzerland

# Timber module school build using modular system

Zug, CH



---

## Temporary school building modules using modular system

We developed a new, standardised modular system for temporary school rooms for the canton of Zug. The basic building block is a prefabricated room cell with a floor area of 25m<sup>2</sup>. As with all of our modular structures, the development standard is very high. For example, it conforms to the Minergie standard. A classroom with a usable area of 75 m<sup>2</sup> comprises three room cells. This allows for various floor plan configurations.

Modul Zug is designed as a living classroom accentuated with strong colours. The school and kindergarten pavilions enable a flexible, rapid response to changing requirements in terms of school, kindergarten and daycare space. The basic modules can be combined according to site-specific requirements over two storeys (extendible to three storeys) in various floor plan layouts.

## Specific Contact



**Migga Hug**

Head of GC & TC Services | Architectural  
planning | Switzerland  
Member of the Division Management

T +41 71 388 58 23  
[migga.hug@blumer-lehmann.com](mailto:migga.hug@blumer-lehmann.com)

# Timber module school build using modular system

Zug, CH



Light-flooded corridor

---



Blue classroom doors add design accents

---

# Timber module school build using modular system



Zug, CH



Bright classrooms

Glass doors link interior and exterior spaces